

## 100 kVA/80 kW UPS POWER POD



- 100 kVA UPS Power POD
- Input & Output Switchgear
- Pre-wired: Input & Output Cam Locks
- N+1 HVAC: Cooling Redundancy

### UPS INFORMATION

Manufacturer	Mitsubishi
Series/Model	9700 Series Model 150
Rating kVA KW	100 kVA / 80 KW
Input Voltage	208V 4W +G
Input Wiring (required on site)	(2) Set 4/0 Cam Lock Connections
Output Voltage	208V 4W +G
Output Wiring (required on site)	(2) Set 4/0 Cam Lock Connections
Wrap-Around Maintenance Bypass	With Kirk Key and Solenoid Key Release

### UPS BATTERY INFORMATION

Battery Type	Energys HX 12-400
Estimated Battery Run-Time	8 Minutes (Standard) – extended runtime options are available.

### HVAC INFORMATION

Manufacturer	AirSys
Number of A/C Units	2
Tonnage Capacity: Per Unit	4 Ton
Total Tonnage Capacity	8 Ton