



550 kVA UPS Trailer



- **550 kVA UPS Power**
- **Input & Output Switchgear**
- **Pre-wired: Input & Output Cam locks**
- **N+1 HVAC: Cooling Redundancy**

UPS INFORMATION

Manufacturer	Eaton
Series/Model	9395-550
Rating kVA KW	550 kVA / 500 KW
Input Voltage	480V 3 or 4W +G
Input Wiring (required on site)	(3) Set 4/0 Cam Lock Connections
Output Voltage	480v 3 or 4W +G
Output Wiring (required on site)	(2) Set 4/0 Cam Lock Connections
Wrap-Around Maintenance Bypass	With Kirk Key and Solenoid Key Release

UPS BATTERY INFORMATION

Battery Type	Northstar NSB 12-730RT
Estimated Battery Run-Time	5 Minutes (Standard)

HVAC INFORMATION

Manufacturer	AirSys
Number of A/C Units	3
Tonnage Capacity: Per Unit	4 Ton
Total Tonnage Capacity	12 Ton