

## CI GROUP 750 kVA/ 750 kW OUTDOOR FLEX POWER MODULE



- Dimensions: 8' wide X 40' long (includes HVAC's) X 9'6" high
- External Cam Lock Connections for customer supplied utility power and UPS output to critical load
- All internal components are pre-configured prior to deployment for ease and speed of deployment
- Cooling Redundancy: cooling is pre-installed and configured for N + 1 Redundancy. Three 4-ton Airsys wall-mount units provide cold supply air at the bottom to promote adequate circulation and effective cooling
- Efficient: our ISO Containers are upgraded with interior insulation and reflective roof paint to insure the proper environment for the power protection equipment



### INTERNAL COMPONENTS

- Mitsubishi 9900B-750 kVA / 750 kW  
Rating: 750 kVA / 750 kW  
Input voltage: 480VAC Three Phase - 3W + Ground  
Output voltage: 480/VAC - Three Phase - 3W + Ground
- Lithium Battery System - 6 minutes at full load 750 kW
- Airsys HVAC Systems (3) N+1
- Sensaphone Remote Monitoring via Cellular Telemetry
- External Maintenance Bypass  
Three Breaker - Kirk Key SKRU Interlock



**CI GROUP**<sup>™</sup>  
CRITICAL INFRASTRUCTURE GROUP

**Marc Basche**  
**818.674.3783 • [mbasche@cigroup-us.com](mailto:mbasche@cigroup-us.com)**  
**[www.cigroup-us.com](http://www.cigroup-us.com)**